

# Superconducting LINAC at Mumbai: an overview




*Prof. R. G. Pillay*

*Department of Nuclear and Atomic Physics*

*Tata Institute of Fundamental Research*

*Mumbai*

*Accelerator layout*



**BARC - TIFR**  
**Heavy Ion Accelerator Facility**


# TIFR-BARC Accelerator Facility

## Pelletron accelerator

- $E/A \sim 3-7$  MeV,  $\beta \sim 0.08-0.12$
- Heavy ions reactions upto  $A \sim 40$

## Superconducting Linac booster

- $E/A \sim 5-12$  MeV,  $\beta \sim 0.10-0.16$
- Heavy ions reactions upto  $A \sim 80$   
(limited by pre-accelerator)
- Beam intensity:  $0.1-10$  pnA ( $10^9-10^{11}$  p/s)  
(limited by ion source)




# Joint TIFR – BARC Project

## Specifications

Heavy ions upto  $A \sim 80$   
 $E/A \sim 5-12$  MeV

Energy gain 14MV/q  
Module 7 nos  
Resonators 28 nos


Bunch width  $\sim 200$  ps  
Beam Intensity 0.1-10 pA



Phase I commissioned on September 22<sup>nd</sup>, 2002  
Phase II commissioned on July 9<sup>th</sup>, 2007  
LINAC dedicated to users on Nov. 28<sup>th</sup>, 2007

*Superbuncher cavity*

Before Plating



After Lead Plating



## Quarter Wave Resonators

**Material**

**OFHC Cu**

**Superconducting surface**

**2  $\mu\text{m}$  thick. Pb**

**Frequency**

**150 MHz**

**Cavity Length**

**64 cm**

**Cavity Diameter**



**20 cm**

**Optimum velocity**


**$\beta=0.1$**

**Design goal**

**2.5 to 3 MV/m  
@ 6 to 9 Watts**




# Module Cryostat




*Top view of the module*



# *He vessel and QWRS*







Cryostat modules housing the resonators with liquid He distribution box

# Cryogenics system for the Linac

**Helium Refrigerator**                      **Linde TCF-50S**  
**Al Plate Fin Heat Exchangers**  
**Two stage Turbine Expansion Engines**  
**Two stage JT Expansion**  
**250 KW Screw Compressor**                      **62 g/s**



**Refrigeration at 4.5 K/Liquification**  
**Without LN<sub>2</sub>**                      **300 W, 50 l/hr**  
**With LN<sub>2</sub> pre-cooling**                      **380 W, 120 l/hr**

The entire cryogenic distribution was fabricated and assembled on-site and has performed as per design.




# RF ELECTRONICS FOR SUPERCONDUCTING RESONATORS

- **RESONATOR CONTROLLER AND CAMAC SYSTEM:**
  - ❖ *IN HOUSE DEVELOPMENT USES EITHER INDIGENOUS OR EASILY AVAILABLE RF MODULES.*
  - ❖ *HIGH PERFORMANCE AND LOW COST.*
  - ❖ *ALSO USED AT IUAC & ANU (CANBERRA).*
- **RF POWER AMPLIFIER:**
  - ❖ *COLLABORATIVE EFFORT OF BEL, BARC-TIFR and NSC*



## RF Controller (schematic)



- RF controller cards based on self excited loop based on phase and amplitude feedback.
- 150 Watts, 150 MHz RF power amplifiers.
- CAMAC based control system.
- Control software on LINUX with Java (master + local stations).

# LINAC Control & information System


## ➤ **USES LINUX OPERATING SYSTEM**

❖ *Open source, freely available quite popular among physics community, stable and most secure.*



## ➤ **WEB BASED DISTRIBUTED CONTROL SYSTEM**

❖ *Can access from intranet using a browser for monitor/control.*


❖ *Uses JAVA as programming language.*




# *Micro-sphere Plate detector for timing*



Energy gain in LINAC phase I




Time Spectrum after Superbuncher



$^{58}\text{Ni} + ^{197}\text{Au} @ 90^\circ$  in lab


24 Jan. 2004



*The first beam was accelerated through the phase I of LINAC Booster on 22<sup>nd</sup> Sept. 2002.*

*Ni Beam acceleration Jan 2004.*

*Longitudinal phase space after mid-bend*




*Beam Diagnostic tests: Feb-March '03.*  
*The first beam cycle: April-May '03.*


*Nuclear physics A770, 126 (2006)*  
*Phys.Rev. C73, 064609 (2006)*



# *Development of Beamline components & Diagnostic elements*



# *LINAC & Experimental Beam Halls*



## *Hall 1*


- Condensed Matter Physics (7 T Magnet) & Atomic, Molecular & Cluster Physics
- General purpose / Irradiation line
- High energy gamma ray & neutron wall

## *Hall 2*


- General Purpose Scattering Chamber
- HP Ge Spectrometer (INGA)
- Charged particle ball
- Magnetic separator for light RIBs



# *User beam Hall I*




## Hall I Experimental stations



# *Exclusive Measurements of GDR in $^{28}\text{Si} + ^{124}\text{Sn}$ @ 188 MeV*


*D.R. Chakrabarty et al.*



- 7 element  $\text{BaF}_2$  detector with plastic anti cosmic shield (for high energy  $\gamma$  rays)
- 38 element BGO multiplicity detector (for angular momentum,  $\epsilon \sim 70\%$ )
- Annular PPAC detector (for residue gating,  $\epsilon \sim 25\%$ )
- HpGe detector (for diagnostic purposes)
- beam  $\sim 1$  pA on target, 5 days


28 Si 13+

(July 07)




# Acceleration through LINAC

July 07



# Some Milestones ...







Dedicated to Users on November 28<sup>th</sup>, 2007



# *TIFR & BARC*

## *Team*

**R.G. Pillay M.B. Kurup B. Srinivasan Vandana Nanal J.N. Karande S. Jangam  
P.B. Thakkar K.S. Parab C. D'Costa L.V. Kamble S.M. Powale V.L. Kadam J.Y. Sathe  
Sudheer Singh Gopal Joshi C.I. Sujo Shyam Mohan Q.N. Ansari S.K. Sarkar  
R.D. Deshpande S.R. Sinha M.S. Pose M.E. Sawant (M.K. Pandey P. Patil)**

## *TIFR*

- Dept of Nuclear And Atomic Physics
- Central Workshop
- Central Services
- Low Temperature Facility

## *BARC*

- Nuclear Physics Division
- Electronics Division
- Central Workshop

## *Vendors*

**IBP • Vacuum Techniques • Aarti Engineering • Fullinger • SMP Enterprises  
Accelerator Consultancy Services • Transact-India/Danfysik • BEL • Sameer  
• Kamal Engineering • BOC Edwards • Pfeiffer**

*Critical components of LINAC booster have been designed, developed and fabricated indigenously.*



*The superconducting LINAC has been a major milestone in the development of accelerator technology in our country.*